

# PRIMARY GRAIN ELEVATOR

Manitoba Pool Elevators

Letellier, Manitoba



## Project Description

KGS Group provided detailed design of a new state-of-the-art grain handling/storage facility for Ellis-Don Construction Ltd., Toronto, in a design-build contract to Manitoba Pool Elevators. The \$9 Million reinforced concrete elevator included the following design features:

- 16,000 tonnes storage capacity, with 40 bin separations
- 4-track rail shipping shed with 25,000 bu/hr capacity
- Truck receiving shed with 2-100 tonne platform scales
- 40,000 bu/hr bulk weigh scale
- Cleaners with 3000 bu/hr capacity
- Grain aeration and fumigation systems